POD XGREENIDGE



GENERAL

• Pod Total kW: 2.8

• Total Dimension: 53' x 16' x 8'6"(Lwh)

Pod dB at 10 (ft): 78
Lead Time: 10-14 wks

• CSC Cert for Shipping: YES

MAIN POD SECTION

• QTY: **1**

• Dimension: 53' x 8' x 8'6" (Lwh)

• Weight: 32000 (lbs)

INTAKES

• QTY: 2

• Dimension and Weight (ea): 53' x 4'x 8'6" (Lwh)

• Weight (ea): 12000 (lbs)

• Weather Protection: **Drainable rain louvers**

• Intake Air Velocity (fpm): 600

• Filters

- QTY: 18

Type: Mesh filter screen

Size: 62" x 98"Reusable: YES

EXHAUST FANS

• QTY: **5**

Mounting: Upblast roof

• Horse Power per: 30

Arrangement: Upblast

• Total CFM: 324,000

• Fan Static Rating (in WC): 0.6

• VFDs: YES

• Temperature Controls and Fan Curves: YES

• PLC/Modbus Ready: YES

• Hot Air Recirculation Potential: NO

MINERS

• QTY: **792**

• QTY of Racks/Panels: 18

Miners per Rack/Panel: 44

• Miner Type Compatibility: S19, XP, S21

Arrangement: Standing up

• Deltas: NA

NETWORK

• Access Switch QTY: 18 (optional)

• Distribution Switch QTY: 2 (optional)

• Pre-Installed Ethernet: YES

TYPICAL POD SPACING

• Intake to Intake: 25'

• Exhaust to Exhaust: NA

ELECTRICAL

Power Distribution from Transformers:

1200A Power Panels (x4)

• Voltage from Power Panels to PDUs: 415/240

Code Compliant: YES

Meets Short Circuit and Arc Flash

Requirements: YES

Separate Disconnect Required: NO

Pre-Installed Y-Cables: YES

• PDUs

■ OTY: 36

• Circuit Protection per PDU: 150A Breakers

Amps per PDU: 150A

■ Short Circuit Protection at PDU: **180A 45kA**

main fuse per PDU

C19 Outlets per PDU: 24

Spare C19 Outlets per PDU: 2

C19 Outlet Circuit Protection: 20A fuse