POD X Greenidge



Standard Size

GENERAL

• Pod Total MW: 2.8

• Total Dimension: 53' x 16' x 8'6"(Lwh)

• Pod dB at 10 (ft): 78

• Lead Time: 12-16 wks

CSC Cert for Shipping: YES

MAIN POD SECTION

• QTY: **1**

• Dimension: 53' x 8' x 8'6" (Lwh)

• Weight: 32000 (lbs)

INTAKES

• QTY: 2

• Dimension and Weight (ea): 53' x 4'x 8'6" (Lwh)

• Weight (ea): 12000 (lbs)

• Weather Protection: Drainable rain louvers

• Intake Air Velocity (fpm): 600

• Filters

■ QTY: 18

Type: Mesh filter screen

Size: 62" x 98"Reusable: YES

EXHAUST FANS

• OTY: 5

Mounting: Upblast roof

• Horse Power per: 30

• Arrangement: Upblast

• Total CFM: **324,000**

• Fan Static Rating (in WC): 0.6

• VFDs: YES

• Temperature Controls and Fan Curves: **YES**

• PLC/Modbus Readv: YES

Hot Air Recirculation Potential: NO

MINERS

 \circ QTY: 792 S19s and XPs / 732 S21 Pros

• QTY of Racks/Panels: 18

• Miners per Rack/Panel: 44

Miner Type Compatibility: S19, XP, S21

Arrangement: Upright

• Deltas: NA

NETWORK

• Access Switch QTY: 18 (optional)

• Distribution Switch QTY: 2 (optional)

Pre-Installed Ethernet: YES

TYPICAL POD SPACING

• Intake to Intake: 25'

• Exhaust to Exhaust: NA

ELECTRICAL

• Power Distribution from Transformers:

1200A Power Panels (x4)

• Voltage from Power Panels to PDUs:

415/240

• Code Compliant: **YES**

• Meets Short Circuit and Arc Flash

Requirements: YES

Separate Disconnect Required: NO

• Pre-Installed Y-Cables: YES

• PDUs

■ OTY: 36

Circuit Protection per PDU: 150A Breakers

■ Amps per PDU: **150A**

■ Short Circuit Protection at PDU: 180A 45kA

main fuse per PDU

C19 Outlets per PDU: 24

Spare C19 Outlets per PDU: 2

■ C19 Outlet Circuit Protection: **20A fuse**

POD X GREENIDGE



20' Size

GENERAL

• Pod Total MW: 1

• Total Dimension: 20' x 16' x 8'6"(Lwh)

 \circ Pod dB at 10 (ft): 78

• Lead Time: 12-16 wks

CSC Cert for Shipping: YES

MAIN POD SECTION

• QTY: **1**

Dimension: 20' x 8' x 8'6" (Lwh)

• Weight: 10000 (lbs)

INTAKES

• QTY: 2

• Dimension and Weight (ea): 20' x 4'x 8'6" (Lwh)

• Weight (ea): 4000 (lbs)

• Weather Protection: Drainable rain louvers

• Intake Air Velocity (fpm): 600

• Filters

■ OTY: **7**

Type: Mesh filter screen

■ Size: **62" x 98"**

Reusable: YES

EXHAUST FANS

• QTY: **2**

Mounting: Upblast roof

• Horse Power per: 30

• Arrangement: Upblast

• Total CFM: **129,600**

• Fan Static Rating (in WC): 0.6

• VFDs: YES

• Temperature Controls and Fan Curves: YES

• PLC/Modbus Readv: YES

Hot Air Recirculation Potential: NO

MINERS

 \circ QTY: 308 S19s and XPs / 284 S21 Pros

• QTY of Racks/Panels: 7

• Miners per Rack/Panel: 44

Miner Type Compatibility: S19, XP, S21

Arrangement: Upright

• Deltas: NA

NETWORK

Access Switch QTY: 7 (optional)

• Distribution Switch QTY: 1 (optional)

• Pre-Installed Ethernet: YES

TYPICAL POD SPACING

• Intake to Intake: 20'

• Exhaust to Exhaust: NA

ELECTRICAL

• Power Distribution from Transformers:

800A Power Panels (x2)

• Voltage from Power Panels to PDUs:

415/240

• Code Compliant: YES

• Meets Short Circuit and Arc Flash

Requirements: YES

Separate Disconnect Required: NO

• Pre-Installed Y-Cables: YES

• PDUs

■ OTY: 14

Circuit Protection per PDU: 150A Breakers

■ Amps per PDU: **150A**

■ Short Circuit Protection at PDU: 180A 45kA

main fuse per PDU

C19 Outlets per PDU: 24

Spare C19 Outlets per PDU: 2

■ C19 Outlet Circuit Protection: **20A fuse**

POD X GREENIDGE



40' Size

GENERAL

• Pod Total MW: 2

• Total Dimension: 40' x 16' x 8'6"(Lwh)

 \circ Pod dB at 10 (ft): 78

• Lead Time: 12-16 wks

CSC Cert for Shipping: YES

MAIN POD SECTION

• QTY: **1**

Dimension: 40' x 8' x 8'6" (Lwh)

• Weight: 21000 (lbs)

INTAKES

• QTY: 2

• Dimension and Weight (ea): 40' x 4'x 8'6" (Lwh)

• Weight (ea): 8000 (lbs)

• Weather Protection: Drainable rain louvers

• Intake Air Velocity (fpm): 600

• Filters

■ QTY: 14

Type: Mesh filter screen

Size: 62" x 98"Reusable: YES

EXHAUST FANS

• QTY: **4**

Mounting: Upblast roof

• Horse Power per: 30

• Arrangement: Upblast

• Total CFM: 259,200

• Fan Static Rating (in WC): 0.6

• VFDs: YES

• Temperature Controls and Fan Curves: YES

• PLC/Modbus Readv: YES

Hot Air Recirculation Potential: NO

MINERS

QTY: 616 S19s and XPs / 568 S21 Pros

• QTY of Racks/Panels: 14

• Miners per Rack/Panel: 44

Miner Type Compatibility: S19, XP, S21

Arrangement: Upright

• Deltas: NA

NETWORK

Access Switch QTY: 14 (optional)

• Distribution Switch QTY: 2 (optional)

Pre-Installed Ethernet: YES

TYPICAL POD SPACING

• Intake to Intake: 20'

• Exhaust to Exhaust: NA

ELECTRICAL

Power Distribution from

Transformers: 800A Power Panels (x4)

• Voltage from Power Panels to PDUs:

415/240

Code Compliant: YES

• Meets Short Circuit and Arc Flash

Requirements: YES

Separate Disconnect Required: NO

• Pre-Installed Y-Cables: YES

• PDUs

■ OTY: 28

Circuit Protection per PDU: 150A Breakers

■ Amps per PDU: **150A**

■ Short Circuit Protection at PDU: 180A 45kA

main fuse per PDU

C19 Outlets per PDU: 24

Spare C19 Outlets per PDU: 2

■ C19 Outlet Circuit Protection: **20A fuse**